

**2017 Christina Drive Improvement Project in Sandusky Township**

**Sandusky County, Ohio**

**Bid Tabulation**

Date: August 15, 2017

Time: 6:00 PM

Estimate: \$115,000.00

**Buckeye Excavating  
& Construction, Inc.  
191 SR 61 East  
Norwalk, Ohio 44857**

Bid Bond

Ref. No.	Spec. No.	Item Description	Quantity	Unit	Unit Price Bid	Total Price
1	103.05	Premium for Contract performance Bond	Lump	Sum	\$1,700.00	\$1,700.00
2	202	Miscellaneous Removals	Lump	Sum	\$3,000.00	\$3,000.00
3	202	Catch Basin Removed	4	Each	\$200.00	\$800.00
4	202	Manhole Removed	1	Each	\$300.00	\$300.00
5	202	Pipe Removal, 12" and under	400	L.F.	\$4.00	\$1,600.00
6	202	Curb & Gutter Removed	1,000	L.F.	\$4.00	\$4,000.00
7	253	Pavement Repair	100	S.Y.	\$43.00	\$4,300.00
8	254	Pavement planing, asphalt concrete	1,250	S.Y.	\$7.00	\$8,750.00
9	407	Tack coat	160	Gal.	\$4.00	\$640.00
10	441	Asphalt concrete intermediate course, Type 2 (448)	215	Ton	\$88.00	\$18,920.00
11	441	Asphalt concrete surface course, Type 1 (448), PG 64-22	95	Ton	\$104.00	\$9,880.00
12	605	6" Base Pipe Underdrains	540	L.F.	\$9.00	\$4,860.00
13	609	Curb & Gutter, Type 3	1,000	L.F.	\$22.00	\$22,000.00
14	611	12" RCP Conduit, (Type B, 706.02)	162	L.F.	\$55.00	\$8,910.00
15	611	12" RCP Conduit, (Type C, 706.02)	213	L.F.	\$51.00	\$10,863.00
16	611	Std. No. 3A Catch Basin	2	Each	\$1,600.00	\$3,200.00
17	611	Std. No. 2-2B Catch Basin	1	Each	\$1,100.00	\$1,100.00
18	611	4" Conduit, (Type E, 707.41-707.45)	50	L.F.	\$4.00	\$200.00
19	611	6" Conduit, (Type E, 707.41-707.45)	50	L.F.	\$5.00	\$250.00
20	611	8" Conduit, (Type E, 707.41-707.45)	50	L.F.	\$6.00	\$300.00
21	611	10" Conduit, (Type E, 707.41-707.45)	50	L.F.	\$7.00	\$350.00
22	611	12" Conduit, (Type E, 707.41-707.45)	50	L.F.	\$11.00	\$550.00
23	614	Maintaining traffic	Lump	Sum	\$1,500.00	\$1,500.00
24	623	Construction Layout Stakes	Lump	Sum	\$3,000.00	\$3,000.00
25	659	Seeding and Mulching	1,000	S.Y.	\$2.00	\$2,000.00
26	Special	Driveway Repair	Lump	Sum	\$12,000.00	\$12,000.00
<b>TOTAL BASE BID:</b>						<b>\$124,973.00</b>